



Trap&Treat BOS200® Case Studies





*Prepared by:
Gabriele Giorgio Ceriani
In-Situ Services Team Leader
Ejlskov A/S*

Case Study #1



Injection Design and Injection Layout Map




Estimated Soil Contaminant
Mass: ~ 30,000 kg
Areal extent: ~ 1,200 sqm
Injection Depths:
5 m bgl to ~13-14 m bgl (bedrock)

Injection Points Map


Two Phases of works were carried out:

- Phase 1 from October to December 2014 (station operational)
- Phase 2 from March to May 2015 (station closed)
- Approx. 287 injection points and 72,000 kg of BOS200® injected



Source and plume treatment – Copenhagen (Active Gas Station) – Case Study – Performance Based Contract


Key Wells Reduction % Trends



Above – overall trends of monitoring wells (Benzene % reduction trends are shown) part of the performance-based contract – from LNAPL concentrations to below site-specific criteria in less than 3 years (1.5 m LNAPL well cleaned to ND levels)

On the right – the importance of removing a migration pathway. Limestone aquifer GW well not addressed by injections. Removal of contaminant migration pathway from the upper soils allowed passive reduction of BTEX concentrations

NO FURTHER ACTION granted by local authorities in June 2018 – Largest EU retail site for the client



Parameter		Sum BTEX	Benzene	Toluene	Xylenes (o+m+p-Xylene +Ethylbenzene)
Quality Criteria		-	1	5	5
Well	Date	µg/l	µg/l	µg/l	µg/l
KB2-B	Feb 2013	4,321	4,200	2	119
KB2-B	Mar 2013	4,900	4,800	< 1,9	77
KB2-B	May 2013	344	330	< 1	14
KB2-B	Aug 2013	385	373	<1,2	12
KB2-B	Nov 2013	264	260	< 2	4
KB2-B	Feb 2014	359	340	< 2	19
KB2-B	May 2014	221	210	< 2	9
KB2-B	Aug 2014	100	96	0.11	6
KB2-B	Dec 2014	360	350	0.28	13
KB2-B	Feb 2015	310	280	5.5	24
KB2-B	Mar 2015	440	420	1	19
KB2-B	Jul 2015	205	200	< 3	< 1,6
KB2-B	Aug 2015	105	98	< 5	< 2,4
KB2-B	Feb 2016	48	42	< 6	< 3,8
KB2-B	May 2016	12	10	<2	< 0,9
KB2-B	Aug 2016	12	9	< 2	< 1,1
KB2-B	Nov 2016	10	7	< 2	< 0,9
KB2-B	Jan 2017	41	7	17	17
KB2-B	May 2017	16	14	1	0.37
KB2-B	Oct 2017	< 0,01	< 0,01	< 0,01	< 0,04
KB2-B	Jan 2018	22	22	0.15	0.79
KB2-B	May 2018	0.16	0.041	<0.02	0.12



Active Gas Station (Copenhagen) – Performance Based Contract



Validation Soil Sampling

VADOSE ZONE			
SAMPLING EVENT	2012	2015	2017
TOTAL TVPH MASS (kg)	18.62	9.07	4.88
% REDUCTION IN MASS		51.3%	73.8%

SATURATED ZONE			
SAMPLING EVENT	2012	2015	2017
TOTAL TVPH MASS (kg)	4.66	0.02	0.85
% REDUCTION IN MASS		99.7%	81.7%



Soil Validation Data from LNAPL location requested by client.

Evaluation based on high resolution soil samples from within the same square meter off the original location sampled in 2012.

Sampling events conducted 3 years post initial pilot test (2012) and 2 years after completion of 2015 full-scale event.



Mass reduction evaluation based on “contaminant mass” evaluation on a cubic meter basis around each soil sample.

By June 2018 MW01-C GW well went from 150 cm LNAPL in 2012 to ND level of Benzene.


Case Study #2



CSM- Post Remedial Design – Injection Summary



Legend



RDC: 20+ MIP Locations performed to 15-20 m bgl - 200 soil samples (50 cm intervals)



Design: Surgical remediation design with 9 specific subareas and injection profiles

In-Situ: 267 injection points from 4 to 15 m bgl within one single injection round (June to August 2015) - Approx. 60,000 kg of BOS200 installed (incl. additional slow release electron acceptor amendments)

Follow-Up: Performance Monitoring (Groundwater and Soil Validation)

Active Gas Station (Finland) – Guarantee Based Contract



Groundwater Performance Monitoring



JOIN OUR MISSION – CLEANING UP THE EARTH

Active Gas Station (Finland) – Guarantee Based Contract

Groundwater Performance Monitoring






LNAPL Site Closed in 3-½ years post injection (1 µg/l Benzene required)

JOIN OUR MISSION – CLEANING UP THE EARTH

Active Gas Station (Finland) – Guarantee Based Contract


Performance Monitoring – Soil Validation



Case Study #3






Source and barrier treatment – LNAPL Case Study



- 35 m3 Xylene Spill in 1985
- LNAPL pushing towards marine environment
- LNAPL observed in few wells prior to remediation start no longer observed after remediation completion
- Injection completed across Q3-Q4 2019
- Site specific criteria to be met on average on-site and off-site

Post-REM
Q4-2022





JOIN OUR MISSION – CLEANING UP THE EARTH

Source and barrier treatment – LNAPL Case Study

Soil Data Overview Pre- and Post Remediation






Soil validation data from the June 2023 event showed a reduction in the TPH soil contaminant mass of approx. 70% compared to pre-remediation soil concentrations (5,000 kg of TPH degraded within 36 months)



Case Study #4



Active Gas Station Sweden – LNAPL Plume Treatment




ELEMENT	SAMPLE	Medelkoncentrationen	Medelkoncentrationen	Reduction
Sampling Date		2018-07-26	2022-01-10	%
alifater >C5-C8	µg/l	929	66.5	93%
alifater >C8-C10	µg/l	236	50.0	79%
alifater >C10-C12	µg/l	22	10.0	55%
alifater >C12-C16	µg/l	20	10.0	50%
alifater >C16-C35	µg/l	44	25.0	43%
aromater >C8-C10	µg/l	2098	36.8	98%
aromater >C10-C16	µg/l	10	5.0	50%
aromater >C16-C35	µg/l	1	2.5	-150%
bensen	µg/l	3459	1.5	100%
toluen	µg/l	4414	4.3	100%
etylbenzen	µg/l	654	5.0	99%
xylen, summa	µg/l	4140	18.2	100%
PAH, summa L	µg/l	38	2.5	
PAH, summa M	µg/l	0.36	0.1	
PAH, summa H	µg/l	0.08	0.0	
MTBE	µg/l	367	0.1	100%
MEDELVÄRDE reduktion samtliga				63%
MEDELVÄRDE reduktion >åtgärds mål				96%

- Injections completed in Q3 2018
- 266 injection points across entire active gas station
- Approx. 30,000 kg of BOS200® installed incl. supplemental electron acceptors
- Plume containment – reduction as main goal based on site specific criteria (long term re-evaluation of risks)


Case Study #5



Residual LNAPL – MTBE Risk Removal (Case Study) – South East Finland




MTBE GA2 & GA2/U




- 425 soil samples analysed free of charge – Sept 2017
- In-situ remediation completed in May - June 2018
- Pre-drilling followed by Direct Push injections (11 m of dry sands to go through)
- Site closed in Q2 2021 – compliance point results on the right

Case Study #6







Case Study – Gas Station Off-Site Plume Mitigation



JOIN OUR MISSION – CLEANING UP THE EARTH



Case Study – Gas Station Off-Site Plume Mitigation

EJLSKOV
Cleaning up the earth




JOIN OUR MISSION – CLEANING UP THE EARTH

Summary of Injection Works




- Total of 238 injection points (April 14th to May 14th 2020)
- Injection depth varying from 1.5 m bgl to 7 m bgl
- Total of 29,000 kg of BOS200® and supplemental slow release terminal electron acceptors
- >80% soil contaminant mass reduction measured via high resolution soil validation event in December 2023




Post Remediation Overview


Totalkulbrinter GW June 2023 Post Remediation




Toluene GW June 2023 Post Remediation




Sum Xylenes GW June 2023 Post Remediation





Post Remediation Overview

EJLSKOV
Cleaning up the earth



JOIN OUR MISSION - CLEANING UP THE EARTH


Case Study #7



Remediation Solution – Soil mixing / blending

Remediation solution / application:

- Excavation pits can be open in small areas (e.g. 5 x 5 m) and slowly advanced to depth with a bucket excavator
- Soil from the clean top layers can be temporarily stock-piled on site
- When contaminated layers are reached, BOS100® / CAT100 / BOS200® slurry and additional terminal electron acceptors or donors can be added to the formation and soil mixed by use of bucket excavator or power mixers
- The contaminated soil can always be mixed inside the excavation pit
- Clean top-soil is compacted at completion of soil mixing operations




JOIN OUR MISSION – CLEANING UP THE EARTH

Case Study – TPH Soil Contamination – Soil Mixing



On the left – Soil contamination prior to BOS200® treatment
Below – Soil condition after soil validation 24 months post treatment (colored areas showing treatment zones)
95% TPH mass reduction measured by collection of high-density soil data compared to pre-remediation soil data



In all executed soil cores, it was possible to confirm presence of BOS200® slurry mixed with the soil within the treatment depths. One example provided to the left

