



In-Situ Remediation by Trap&Treat BOS100[®]/CAT100 – DNAPL Redevelopment Site Sweden



Gabriele Giorgio Ceriani
In-Situ Remediation Services Team Leader
Ejlskov A/S

Key Summary Information

High Resolution Remedial Design Characterization performed in April 2019 including:

- 58 MIP Points
- 20 Dual Tube Undisturbed Soil Cores (250 high-density soil samples (every 50 cm or less) analysed free of charge)
- 12 GW Monitoring Wells

Price per m3 of soil investigated: < 15 SEK/m3

Additional 14 undisturbed soil cores performed in 2021 with 150 extra high-density soil samples collected (to define excavation zone around MW49) and 5 extra monitoring wells completed during remediation mobilization.

Total of ~400 soil samples (over entire project lifetime) analysed for free leading to an approximate 350-400,000 SEK cost saving



In-situ Remediation completed in September 2021 including:



- Treatment area of approx. 900 sqm
- Indirect treatment of soil and groundwater downstream of injections area (see GW results)
- Use of CAT100 for source treatment and BOS100® for barrier zone

Average treatment cost: ~930 SEK/m3 or 490 SEK/ton


Approx. 200 groundwater samples analysed free of charge by RPI Lab in Denver Colorado post injection. Commercial value of RPI Lab package per sample: ~2,500 SEK/sample (incl. VOCs, CVOCs, anions, fatty acids, dissolved gases) 500,000 SEK approx. cost saving (only shipment and admin costs charged to client each monitoring event).



MIP Investigation – Bedrock Delineation




JOIN OUR MISSION – CLEANING UP THE EARTH




Soil and GW Contamination Conditions

Upper contaminant profile in cross section shows soil contamination extent
Lower contamination profile shows the GW plume



JOIN OUR MISSION



Injection Plan Layout



- Total number of points: 205
- Injection depths: 3.5 / 4 m bgl to bedrock
- CAT100 used in the source area around MW49 and directly downstream (MW33 and MW46 area)
- BOS100® used at site boundary as PRB solution to ensure control of plume migration offsite
- DNAPL contaminated soil in the upper layers of MW49 area (3.5-4.0 m bgl) left untreated in agreement with client as part of the excavation plan for construction of underground parking



Pre Treatment vs. Post Treatment






JOIN OUR MISSION – CLEANING UP THE EARTH

Site Pictures

EJLSKOV
Cleaning up the earth




CVOCs GW Concentrations Pre- and Post Injection




JOIN OUR MISSION - CLEANING

Ethylene GW Concentrations Pre- and Post Injection

Pre-Injection Q3 2021



Post-Injection Q4 2023



OBS – Ethylene results provide evidence of on-going full conversion of mother products to non-hazardous end products. The higher the concentrations, the higher the intensity of biological activity. Off-site ethylene generation at MW103 and GV7 indicates presence of TCE off site soil contaminant mass being indirectly degraded as an effect of CAT100 injections



Ejlskov
ejlskov.com